

MAY 24 2000

LIBER 21119 645

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

51709

For corners in

<u>Oakland</u> (county)	Located In: Rose Township	Corner Code # G-6
1. Public Land Survey	T4N R7E	G-6
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	_____
	S___ T___	_____
3. Miscellaneous Property in Sec.	S___ T___	_____
	S___ T___	_____

LIBER 21119 PAGE 645  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 02/18/2000 02:36:27 P.M. RECEIPT# 14203  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

ACT 74, P.A. 1970  
 4-21-99 54  
 OAKLAND COUNTY REMONUMENTATION  
 BOARD COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	8	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There is one LCRC recorded at Oakland County; Hart 1996.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 5/8" iron at this location. The iron as located agrees with the LCRC recorded by Hart in 1996, but will not agree with record distances on the north line of S/P #5 by 2.30'. The iron as recovered will agree with monumentation north of its location. Since the monumentation that was recovered in the S/P will not agree entirely within itself, I recommend the location of this corner stay with its current monumentation.

\*Recovered Witnesses:

- \*N 05°E 12.65' PK nail west side 3" Maple.
- \*S 80°W 7.25' PK nail north side 4" Poplar.
- \*S 00°E 17.65' PK nail east side 4" Poplar.
- \*N 45°W 30.10' PK east side 6" Maple.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 05°E 12.65' Mag nail with OCRT #24598 west side 3" Maple.
- S 80°W 7.25' Mag nail with OCRT #24598 north side 4" Poplar.
- S 00°E 17.65' Mag nail with OCRT #24598 east side 4" Poplar.
- N 45°W 30.10' Mag nail with OCRT #24598 east side 6" Maple.

\*Reused Recovered Witness



Signed by Joseph C. Kapelczak  
 Surveyor's Michigan License No. 24598

Date 4/19/99