

MAY 24 2000

LIBER 20657 - 350

374957

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20657 PAGE 350  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
10/12/1999 08:06:33 A.M. RECEIPT# 88906  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEED

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	G-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 5-5-99 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims  
\_\_\_\_\_

I, Joseph C. Kapelczak, In a field survey on April 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.

There are four LCRC's recorded at Oakland County; Albright 1973, McMahon 1977, McMahon 1979, and Thompson 1991.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron in DeMode Road at this location. This location was validated with monumentation recovered in the Thompson 1991 survey in Section 21.

\*Recovered Witnesses:

\*North 47.70' found PK nail west side 15" Cherry.

\*N 51°E 40.14' found double-headed nail with tag #23828 in northwest corner wooden fence post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron rod with Oakland County Remonumentation Brass Cap stamped #24598 in gravel road.

Set Witnesses:


\*N 51°E 40.14' Mag nail with OCRT #24598 tag northwest corner wooden fence post.

\*North 47.70' Mag nail with OCRT #24598 tag in west side 15" Cherry.

S 80°W 97.67' Mag nail with OCRT #24598 tag southeast side 10" Walnut.

S 25°W 34.76' Mag nail with OCRT #24598 tag west side 14" Box Elder.

\*Reused Recovered Witnesses



Signed by Joseph C. Kapelczak

Date 5/5/99

Surveyor's Michigan License No. 24598

2P  
R