

SLAVEY & REMONUMENTATION

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

127805

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	H-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21403 PAGE 389  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
05/19/2000 10:35:44 A.M. RECEIPT# 36329  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 4-27-99 - JS  
OAKLAND COUNTY REMONUMENTATION  
REGISTER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		3		2		1						
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are no LCRC's recorded at Oakland County

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. This corner was re-established using recorded deed distances from a recovered monument at H-6 and an iron found at I-7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 70°E 61.19' Mag nail with OCRT #24598 southeast side 18" Oak.
- S 87°W 12.78' Mag nail with OCRT #24598 north side 14" Cherry.
- S 65°E 34.68' Mag nail with OCRT #24598 north side 28" Oak.
- S 29°W 49.57' Mag nail with OCRT #24598 north side 30" Oak.

JS  
R



Signed by Joseph C. Kapelczak

Date 5/18/2000

Surveyor's Michigan License No. 24598