

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

374963

SECTION

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	H-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 20657 PAGE 362  
49.00 MISC RECORDING  
42.00 REMONUMENTATION  
10/12/1999 08:06:33 A.M. RECEIPT# 80906  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 7-7-99 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on April 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There is one LCRC recorded at Oakland County; Ward 1991.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron with Grant Ward cap at the extensions of Perry Road and Wafer Road. Also recovered two witnesses from the previously recorded LCRC of Ward in 1991. No other evidence validating the corner was recovered in the immediate area.

Recovered Witnesses:

- S 70°E 17.12' PK nail south side 12" Oak.
- \*N 20°E 33.39' PK nail with Grant Ward tag northwest side 12" Oak.
- \*N 25°W 40.48' PK nail with Grant Ward tag northeast side 18" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset 5/8" iron rod with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 60°W 46.85' nail with OCRT #24598 north side Twin 8" Oak.
- S 70°E 17.12' nail with OCRT #24598 south side 12" Oak.
- \*N 20°E 33.39' nail with OCRT #24598 northwest side 12" Oak.
- \*N 25°W 40.48' nail with OCRT #24598 northeast side 18" Oak.

\*Reused Recovered Witnesses



2P  
R.

Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 7/8/99