

MAY 24 2000

LIBER 19616PG283

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	I-3
	T R	
	T R	
	T R	
2. Property Controlling S	T R	
in Section S	T R	
3. Miscellaneous S	T R	
Property in Sec. S	T R	

\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/01/1999 02:59:15 P.M. RECEIPT# 4397
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CARDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 02-03-99 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on August 5, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.

There is one LCRC's recorded at Oakland County; Albright 1973. Witnesses were recovered and are shown in Section "B" of enclosed Oakland County LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron Rattalee Lake Road at this location. This location was validated with monumentation recovered along north and south R.O.W. of Rattalee Lake Road west of this corner.

Recovered Witnesses:

- S 47°W 22.04' nail northwest side guard post.
- S 05°E 27.55' nail west side power pole.
- S 62°E 30.29' nail with cap #24607 northeast side guard post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 in new monument box.

Set Witnesses:

- S 47°W 22.04' Mag nail with OCRT stamped #24598 northwest side guard post.
- S 05°E 27.55' Mag nail with OCRT stamped #24598 west side power pole.
- S 22° E 16.29' Mag nail with OCRT stamped #24598 west side guard post.
- S 62°E 30.29' Mag nail with OCRT stamped #24598 northeast side guard post.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

900 FILE
200
ZPR



Signed by Joseph C. Kapelczak

Date 2/1/99

Surveyor's Michigan License No. 24598