

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74; Mich. P.A. 1970

131656

SECTION

For corners in

<u>Oakland</u> (county)	Located in:	Corner Code #
	<u>Rose Township</u>	
1. Public Land Survey	T4N R7E	1-5
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

LIBER 19843 PAGE 667  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 04/16/1999 08:59:50 A.M. RECEIPT# 19968  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 3-31-99 JS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		5		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		18		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There are five LCRC's recorded at Oakland County; Albright 1972, bolt, Smith 1977, PK, Ward 1980, iron, Newman 1992, 1/2" iron and Bonno 1996, 1/2" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron in asphalt in Davisburg Road at this location. This location was validated with monumentation recovered along R.O.W. of Davisburg Road east and west of the corner and along R.O.W. of Oakhurst Road south of the corner. Corner witnesses were found and are shown with measurements in Section "B" of the enclosed Oakland County LCRC.  
 Recovered Witnesses:

- N 28°E 50.79' nail with tag #40162 west side 12" Maple.
- N 36°E 64.27' nail with tag # 10057 west side power pole.
- S 45°E 61.23' nail with Tri-County tag northeast side 10" Locust.
- S 45°E 61.77' nail with tag # 40162 southwest side 10" Locust.
- S 33°W 43.43' nail with tag #40162 southeast side power pole.
- N 32°W 56.21' nail with tag #40162 southwest side power pole.
- N 32°W 56.44' PK with Tri-County tag southwest side power pole.

2p  
R

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 in new monoument box.

Set Witnesses:

- N 11°E 133.51' nail with OCRT stamped #24598 east side 20" Oak.
- N 75°W 90.44' nail with OCRT stamped #24598 northeast side 12" Elm.
- S 70°W 68.88' nail with OCRT stamped #24598 north side 12" Pine.
- S 30°E 62.85' Mag nail with OCRT stamped #24598 east side 12" Elm.



Signed by Joseph C. Kapelczak

Date 3/31/99

Surveyor's Michigan License No. 24598