

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

374967

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	I-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 20657 PAGE 370
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 10/12/1999 08:06:33 A.M. RECEIPT# 88906
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 5-5-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on February 20, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are two LCRC's recorded at Oakland County; Albright 1978 and Ward 1981.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron at intersection of Oakhurst and Rosell Road at this location. This location was validated with monumentation recovered from Ward 1981 survey of Section 23 along with monumentation on the R.O.W. of Oakhurst Road, north of corner. Two witnesses were recovered on the Ward LCRC and one witness was recovered on the Albright LCRC.

Recovered Witnesses:

- N 35°E 40.30' nail with tag #24607 northwest side 18" Oak.
- *N 35°E 40.31' nail in northwest side 18" Oak.
- S 00°E 24.09' nail with tag #24607 west side 12" Oak.
- *S 62°W 43.23' nail with tag #10057 north side power pole.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- *N 35°E 40.30' Mag nail with OCRT #24598 northwest side 18" Oak.
- S 64°E 41.61' Mag nail with OCRT #24598 north side 12" Oak.
- Due South 24.09' Mag nail with OCRT #24598 west side 12" Oak.
- *S 62°W 43.23' Mag nail with OCRT #24598 north side power pole.

A	B	C	D	E	F	G	H	I	J	K	L
2	3	4	5	6	7	8	9	10	11	12	13
3	4	5	6	7	8	9	10	11	12	13	14
4	5	6	7	8	9	10	11	12	13	14	15
5	6	7	8	9	10	11	12	13	14	15	16
6	7	8	9	10	11	12	13	14	15	16	17
7	8	9	10	11	12	13	14	15	16	17	18
8	9	10	11	12	13	14	15	16	17	18	19
9	10	11	12	13	14	15	16	17	18	19	20
10	11	12	13	14	15	16	17	18	19	20	21
11	12	13	14	15	16	17	18	19	20	21	22
12	13	14	15	16	17	18	19	20	21	22	23
13	14	15	16	17	18	19	20	21	22	23	24



2P
R

Signed by Joseph C. Kapelczak
 Surveyor's Michigan License No. 24598

Date 5/4/99