

MAY 24 2000

LIBER 20657 374

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

374969

For corners in

<u>Oakland</u> (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	I-10
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	R___
	S___ T___	R___
3. Miscellaneous Property in Sec.	S___ T___	R___
	S___ T___	R___

LIBER 20657 PAGE 374  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 10/12/1999 08:05:33 A.M. RECEIPT# 88906  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 8-17-99 JL  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on April 17, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There are two LCRC's recorded at Oakland County; Albright 1973 and Dekeysher 1984.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

There are no LCRC's recorded at Oakland County.

Recovered 1/2" iron in monument box in Milford Road at this location. This location was validated with monumentation recovered along the R.O.W. of Milford Road south of the section corner.

Recovered Witnesses:

- N 29°W 49.32' PK nail with RCOC tag northeast side 26" Oak.
- N 42°E 46.33' spike northwest side 20" Oak.
- S 56°E 34.30' spike southwest side 12" Maple.
- S 77°W 33.23' double-headed nail with RCOC tag south side 6" Poplar. (Dead)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 on existing 1/2" iron in the monument box.

Set Witnesses:

- N 29°W 49.32' Mag nail with OCRT #24598 northeast side 26" Oak.
- N 42°E 46.33' Mag nail with OCRT #24598 northwest side 20" Oak.
- S 56°E 34.30' Mag nail with OCRT #24598 southwest side 12" Maple.
- S 67°W 33.75' Mag nail with OCRT #24598 south side 8" Maple.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	6	7	8	9	10	11	12	13	14	15	16	17
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	13	14	15	16	17	18	19	20	21	22	23	24	25
9													
10	16	17	18	19	20	21	22	23	24	25	26	27	28
11													
12	19	20	21	22	23	24	25	26	27	28	29	30	31
13													

*Lp*  
*R*

Signed by Joseph C. Kapelczak

Date 8/3/99

Surveyor's Michigan License No. 24598

