

SURVEY & REMONUMENTATION

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

374971

LIBER 20657 PAGE 378
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 10/12/1999 08:06:33 A.M. RECEIPT# 88906
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

SECTION

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	I-12
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	_____
	S___ T___	_____
3. Miscellaneous Property in Sec.	S___ T___	_____
	S___ T___	_____

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 8-17-99 JJK
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 18, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:
NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are two LCRC's recorded at Oakland County; Albright 1973 and Platz 1996.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" square bolt in asphalt buried 3" below asphalt surface at this location. This location was validated with monumentation recovered on the east side of Milford Road per Ward survey along with recovered witnesses of the above-referenced LCRC's.

Recovered Witnesses:

- *N 55°E 34.73' spike south side 24" Oak.
- *S 63°E 67.90' PK nail with Spaulding DeDecker tag south side power pole.
- S 20°W 84.22' PK nail east side 24" Oak.
- *S 67°W 53.17' spike south side old power pole.
- *S 67°W 52.72' nail with tag #5390 southeast side old power pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron rod with Oakland County Remonumentation Brass Cap #24598 inside of new monument box.

Set Witnesses:

- *N 55°E 34.73' Mag nail with OCRT #24598 south side 24" Oak.
- *S 63°E 67.90' Mag nail with OCRT #24598 south side power pole.
- S 20°W 84.22' Mag nail with OCRT #24598 east side 24" Oak.
- S 67°W 85.29' Mag nail with OCRT #24598 south side new power pole.

* Re-used recovered witnesses.



Signed by Joseph C. Kapelczak

Date 8/3/99

Surveyor's Michigan License No. 24598