

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

127806

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	J-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21403 PAGE 391
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 05/19/2000 10:35:44 A.M. RECEIPT# 36329
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 5-25-00 JJK
 OAKLAND COUNTY REMONUMENTATION
 Register of Deeds Stamp & Filer Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on February, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. This corner was re-established utilizing a single proportional method from I-1 to K-1, being set on the township line between J-13 and I-13. This corner as set is 13.14' west of J-13 Holly township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 18°W 28.04' Mag nail with OCRT #33138 south side 14" Elm.
- N 42°E 33.34' 20 Penny nail with OCRT #24598 southeast side 8" Elm.
- S 33°E 13.28' Mag nail with OCRT #33138 north side 6" Poplar.
- S 80°W 27.13' Mag nail with OCRT #24598 south face of 2 sawed off power poles.
- West 32.66' J-13 Holly Township.

zk
rk



Signed by Joseph C. Kapelczak

Date 5/18/2000

Surveyor's Michigan License No. 24598