

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 19616PG285

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	J-3
	T R	
	T R	
	T R	
2. Property Controlling S	T R	
in Section S	T R	
3. Miscellaneous S	T R	
Property in Sec. S	T R	

\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
03/01/1999 02:59:15 P.M. RECEIVED  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER

MR-199903081170

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 2-3-99 JS  
LAND AND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on August 5, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There is one LCRC recorded at Oakland County; Albright 1973. Witnesses were recovered and are shown in Section "B" of enclosed Oakland County LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a bent 1/2" iron in Rattalee Lake Road at this location. This location was validated with monumentation recovered along R.O.W. lines of Rattalee Lake Road west of this corner.

Recovered Witnesses:

S 62°E 36.08' found nail north side Twin 22" Cherry.  
N 37°E 35.24' nail southwest side triple 18" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

S 62°E 36.08' Mag nail with OCRT stamped #24598 north side twin 22" Cherry.  
S 15°E 22.12' Mag nail with OCRT stamped #24598 east side 10" Elm.  
S 35°W 24.90' Mag nail with OCRT stamped #24598 northwest side 10" Elm.  
N 27°W 15.99' nail with OCRT stamped #24598 southwest side 12" Cherry.



9.00 FILE  
2.00

2pr

Signed by Joseph C. Kapelczak

Date 2/5/99

Surveyor's Michigan License No. 24598