

MAY 24 2000

LIBER 19843PG661

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

131653

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 19843 PAGE 661
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 04/16/1999 08:59:50 A.M. RECEIPT# 19968
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 3-31-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There is one LCRC recorded at Oakland County; Platz 1996.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron with cap #10057 and pinched pipe at this location. This location was validated with monumentation recovered along the south line of the township and Boss Engineering Survey in Section 35.

Recovered Witnesses for capped iron:

- *N 45°E 29.84' nail west side 20" Oak
- S 30°W 16.44' PK nail west side 6" Ash
- N 05°E 13.63' PK south side 10" Poplar
- *S 45°E 14.29' nail west side 18" Oak
- S 45°W 47.80' nail east side 30" Oak
- *N 40°W 8.44' nail east side 8" Ash
- *West 32.77' nail south side 10" Poplar (dead)
- N 65°W 18.90' PK south side 10" Poplar
- West 32.77' PK tag #17623 south side 10" Poplar
- S 55°W 48.18' PK tag #17623 east side 30" Oak
- S 45°E 13.65' PK tag #17623 north side 18" Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" capped iron with OCR brass cap stamped #24598.

Set Witnesses:

- N 45°E 29.84' nail in OCRT #24598 west side 20" Oak.
- S 45°E 14.29' nail in OCRT #24598 west side 18" Oak.
- N 40°W 8.44' nail in OCRT #24598 east side 8" Ash.
- West 32.77' nail in OCRT #24598 south side 10" Poplar.



Signed by Joseph C. Kapelczak Date 3/27/99

Surveyor's Michigan License No. 24598