

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

127807

For corners in

<u>Oakland</u> (county)	Located In: Rose Township	Corner Code # K-13
1. Public Land Survey	T4N R7E	K-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21403 PAGE 393
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 05/19/2000 10:35:44 A.M. RECEIPT# 36329
 PAID RECORDED - OAKLAND COUNTY
 B. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 3-13-99 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on January 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. This corner was re-established by using the southwest corner of Parcel 06-35-400-012 and J-13 along with the record distances as recorded on the deeds. K-1 of Highland Township is located west 176.61' of K-13 Rose Township.

Recovered Witnesses:

N 57°W 29.04' double headed nail with tag #12584 southwest side 30" Oak.
 S 30°W 26.84' double headed nail with tag #12584 northwest side 30" Cherry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Cap stamped #24598.

Set Witnesses:

N 57°W 29.04' Mag nail with OCRT #24598 southwest side 30" Oak.
 S 54°W 40.92' Mag nail with OCRT #24598 northwest side 16" Oak.
 S 30°W 26.84' Mag nail with OCRT #24598 northwest side 30" Cherry.
 S 22°E 35.57' Mag nail with OCRT #24598 northeast side 12" Ash.
 West 176.61' K-1 Highland Township.

2p
R



Signed by Joseph C. Kapelczak
 Surveyor's Michigan License No. 24598

Date 5/18/2000