

MAY 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

127808

For corners in

Table with columns: Oakland (county), Located In: Rose Township, Corner Code #, and survey details (Public Land Survey, Property Controlling, etc.)

LIBER 21403 PAGE 395
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
05/19/2000 10:35:44 A.M. RECEIPT# 36329
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-29-99 SR
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on March 13, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded at Oakland County; Ward 1977.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 3/4" pipe 4.34' south of the Holly Township line and 37.01' west of L-13 Holly Township. This location was validated with monumentation recovered from Ward's 1993 survey of Section 1. Set 5/8" rod with Oakland County Remonumentation Brass Cap stamped #24598 on the Holly Township line.

Recovered Witnesses:

- S 70°E 78.03' PK nail with Grant Ward Tag north side 48" Oak.
S 70°E 78.55' double headed nail in northeast side 48" Oak.
S 70°E 78.55' nail with tag marked "Survey Point #123" northeast side 48" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rod with Oakland County Remonumentation Brass Cap stamped #24598 in gravel road 4.34' north of 3/4" pipe.

Witnesses to the amended corner on the Township Line:

- N 77°W 64.96' Mag nail with OCRT #24598 south side 12" Hickory.
S 26°W 33.50' Mag nail with OCRT #24598 northwest side 6" Oak.
N 44°E 24.46' Mag nail with OCRT #24598 northwest side twin 10" Hickory.
S 71°E 79.35' Mag nail with OCRT #24598 north side 48" Oak.

Witnesses to the recovered closing corner 3/4" pipe:

- N 70°W 66.23' Mag nail with OCRT #24598 south side 12" Hickory.
S 40°W 19.82' Mag nail with OCRT #24598 northwest side 6" Oak.
N 36°E 27.68' Mag nail with OCRT #24598 northwest side twin 10" Hickory.
S 70°E 78.03' Mag nail with OCRT #24598 north side 48" Oak.



Signed by Joseph C. Kapelczak Date 5/15/2000
Surveyor's Michigan License No. 24598