

MAY 24 2000

LIBER 20657 398

SECTION

374981

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20657 PAGE 398  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
10/12/1999 08:06:34 A.M. RECEIPT# 88906  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (county)	Located In: Rose Township	Corner Code # L-11
1. Public Land Survey	T4N R7E	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 7-7-99 JIK  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on April 13, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron at this location. This location was validated with monumentation recovered on Section Line west of corner.

Recovered Witnesses:

- S 75°W 44.64' PK nail with tag #17623 north side 10" Elm.
- N 55°W 20.55' PK nail with tag # 17623 south side 6" Yellow Birch.
- N 20°W 9.28' PK nail with tag #17623 east side 6" Yellow Birch.
- N 20°W 9.18' Double-headed nail east side 6" Yellow Birch.
- East 21.53' PK nail with tag #17623 north side 16" Yellow Birch.
- East 21.35' Double-headed nail north side 16" Yellow Birch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 in top of concrete monument.

Set Witnesses:

- East 21.53' nail with OCRT #24598 north side 16" Yellow Birch.
- N 55°W 30.55' nail with OCRT #24598 east side 6" Yellow Birch.
- N 20°W 9.28' nail with OCRT #24598 south side 6" Yellow Birch.
- S 75°W 44.64' nail with OCRT #24598 north side 10" Elm.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	18	19	20	21	22	23	24	25	26
7											
8	19	20	21	22	23	24	25	26	27	28	29
9											
10	30	29	28	27	26	25	24	23	22	21	20
11											
12	31	32	33	34	35	36	37	38	39	40	41
13											

2p  
12

Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 7/2/99

