

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

127809

For corners in

Oakland (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	L-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21403 PAGE 397
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
05/19/2000 10:35:44 A.M. RECEIPT# 36329
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 3-13-99 JCS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on January 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. This corner was reestablished by establishing the 1/8 corner on the township line between M-13 and L-13 and then doubling the distance between the set 1/8 corner and M-13. L-13 was set on the line between M-13 and K-13. L-1 of Highland Township is 127.47' west of K-13 Rose Township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rod with Oakland County Remonumentation Brass Cap stamped #24598 in root of tree.

Set Witnesses:

- N 73°E 35.29' Mag nail with OCRT #24598 south side 4" Hickory.
- N 02°E 10.34' Mag nail with OCRT #24598 east side clump of five 12" Cherry trees.
- N 67°W 24.97' Mag nail with OCRT #24598 northeast side clump of six 12" Cherry trees.
- N 83°W 54.50' Mag nail with OCRT #24598 south side 24" Cherry.
- East 127.47' L-1 Highland Township.

2p
h



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 5/18/2000