

MAY 24 2000

LIBER 21146 098

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

59640

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Rose Township	
1. Public Land Survey	T4N R7E	M-5
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

LIBER 21146 PAGE 98  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
02/29/2000 10:58:27 A.M. RECEIPT# 16511  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Approved on  
ACT 345, P.A. 1990

APPROVED ON: 11-30-99 JTL  
OAKLAND COUNTY REGISTER OF DEEDS  
PETER CRONIN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on August 5, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There is one LCRC recorded at Oakland County; Ward 1987.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a concrete monument with Oakland County Remonumentation Brass Cap #22445 set by Grant Ward. Mr. Ward placed this concrete monument where he had originally found a 1/2" hexagon iron rod in 1987. Validated the placement of this monument with monumentation found in Mr. Ward's survey recorded in L 10358 P 518.

Recovered Witnesses:

N 70°W 29.88' PK nail with Grant Ward washer south side 18" Hickory (Dead).  
S 70°E 16.40' PK nail with Grant Ward tag north side 18" Hickory (Dead).  
S 05°W 46.44' PK nail with Grant Ward tag southwest side 15" Cherry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Recovered concrete monument with Oakland County Remonumentation Brass Cap #22445.

Set Witnesses:

S 10°W 63.31' Mag nail with OCRT #22445 in a Walnut tree.  
S 45°W 35.90' Mag nail with OCRT #22445 southeast side 12" Elm.  
N 80°W 20.17' Mag nail with OCRT #22445 north side 8" Elm.  
N 40°E 53.13' Mag nail with OCRT #22445 northwest side 10" Elm.



Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 12/22/99