

MAY 24 2000

LIBER 21146 100

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

59641

For corners in

<u>Oakland</u> (county)	Located In: Rose Township	Corner Code #
1. Public Land Survey	T4N R7E	M-6
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___	_____
	S___ T___	_____
3. Miscellaneous Property In Sec.	S___ T___	_____
	S___ T___	_____

LIBER 21146 PAGE 100  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
02/29/2000 10:58:27 A.M. RECEIPT# 16514  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Complies with  
ACT 345, P.A. 1990

APPROVED ON: 11-30-99 JSL  
OAKLAND COUNTY REGISTER GENERAL  
FILE # 245

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on February 26, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are two LCRC's recorded at Oakland County; Scharl 1978 and Frisch 1995.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered iron set by Scharl with cap #19843 as per LCRC L 7177 P 594. Validated its location with witnesses found in the above LCRC and monumentation found in Ward's survey L 10458 P 518. It should be noted that A-6 of Springfield Township is 235.73' north of this corner.

Recovered Witnesses:

West 25.66' PK nail in north side 24" Oak.  
\*N 78°W 11.81' PK nail north side 12" Hickory  
\*S 05°E 18.05' PK nail with Grant Ward washer east side Hickory (12")  
Fence lines running north, south and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass cap stamped #24598.

Set Witnesses:

West 25.66' Mag nail with OCRT #24598 north side 24" Oak.  
N 15°E 12.95' Mag nail with OCRT #24598 east side 6" Hickory.  
\*N 78°W 11.81' Mag nail with OCRT #24598 north side 12" Hickory.  
\*S 05°E 18.05' Mag nail with OCRT #24598 east side 12" Hickory.

\*Reused Recovered Witnesses



Signed by Joseph C. Kapelczak

Date 12/22/99

Surveyor's Michigan License No. 24598