

MAY 24 2000

LIBER 19832 PG 751

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

128319

For corners in

Oakland

(County)

Located in:

Corner Code #

1. Public Land Survey

T	4N	R	8E	A-10
T		R		
T		R		
T		R		
S		T		
S		T		
S		T		
S		T		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LIBER 19832 PAGE 751  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
04/14/1999 01:54:01 P.M. RECEIPT# 189  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 2-11-99 55  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Grant J. Ward, R.L.S., in a field survey on August 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				1
3													
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-10 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 West 1/4 Corner of Section 30, T. 4 N., R. 8 E. Found 1/2 Iron Rod.

Previously Recorded in L. 10847 P. 711 (4) of Oakland County Records.

This corner location, although not established by an original government survey, is accepted as the best available evidence of the position of the corner.

C. Description of Monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 Set Monument and Remonumentation Cap.

N 30° E	29.68'	Set 60d Nail & Remonumentation Disc in Southeast face of 12" Maple.
S 50° E	12.99'	Set 60d Nail & Remonumentation Disc in Northeast face of 12" Ash.
West	29.10'	Set 60d Nail & Remonumentation Disc in North face of 18" Oak.
N 30° W	13.06'	Set 60d Nail & Remonumentation Disc in Northeast face of 12" Oak.
South	85.34'	Found Iron Rod & Cap #22445 East 1/4 Corner Section 25, Rose Township.



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 22445

Date February 9, 1999