

SURVEY &  
REMONUMENTATION

LIBER 19237PG852

MAR 11 1999

LAND CORNER RECORDATION CERTIFICATE \$ 9.00 MISCELLANEOUS RECORDING  
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in SECTION

4 DEC 98 8:30 A.M. RECEIPT  
PAID G. WILLIAM CADWELL  
CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 1-20-98 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

| Oakland<br>(County)                   | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey                 | T 4NR 8E    | B-5           |
|                                       | T R         |               |
|                                       | T R         |               |
|                                       | T R         |               |
| 2. Property Controlling<br>in Section | S T R       |               |
|                                       | S T R       |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R       |               |
|                                       | S T R       |               |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Grant J. Ward, R.L.S., in a field survey on January 14-19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

B-5 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 North 1/4 Corner of Section 18, T. 4 N., R. 8 E. Nothing Found. Used single proportion measurement for setting monument between C-5 and A-5.

Previously Unrecorded.


This corner location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-5 Set Concrete Monument with Remonumentation Cap at Reference Point on Section Line 520.18' of B-5.
- N 65° E 21.13' Set MAG Nail & Remonumentation Disc in East face of 3" Elm.
  - S 15° E 240.06' Set MAG Nail & Remonumentation Disc in North face of 16" Elm.
  - S 17° 48' 27" W 840.93' Set MAG Nail & Remon Disc in C/L of RR Tracks 4185' W'ly along C/L of Tracks from C/L of Eaton.
  - S 36° 28' 43" W 873.65' Set MAG Nail & Remon Disc in C/L of RR Tracks 4465' W'ly along C/L of Tracks from C/L of Eaton.

Signed by [Signature]  
Surveyor's Michigan License No. 22445

Date January 22, 1998



900 FILE  
200

SURVEY &  
REMONUMENTATION

LIBER 19237 PG 853

MAR 11 1999

SECTION

JANUARY 15, 1998

Corner Code: B-5

DOSSIER FOR: THE SOUTH 1/4 CORNER OF SECTION 7, SPRINGFIELD TOWNSHIP, T 4 N, R 8 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

HISTORY:

The boundary of this Township was surveyed by Alex Holmes, D.S. in 1815 and Joseph Wampler, D.S. set the Corners for the subdivision of it in 1823.

SPECIAL NOTES:

We set this Corner by single proportion measurement and on line with A-5 and C-5. This Corner has not been previously recorded.

COLLATERAL EVIDENCE:

This Corner lies in a lake. We set a Reference Monument 520.18 feet Easterly of the Corner and on the Section Line. There is no evidence of occupation near this Corner. The measured dimensions agree with the GLO distances within about 15 feet.

SURVEYOR'S RECOMMENDATIONS:

The selected location is accepted by the Contractor and is generally accepted by Professional Surveyors as the best available evidence of the position of the original Corner. Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

---

Grant J. Ward, R.L.S.  
License No. 22445