

MAY 24 2000

SECTION

LIBR 19237PG872
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Oakland (County) Located in: Corner Code #

1. Public Land Survey	T 4N R 8E	D-1
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

\$ 9.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 4 DEC 98 8:32 A.M. RECEIPT# 48
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CAIDELL
 CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 4-28-98 53
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Grant J. Ward, R.L.S., in a field survey on November 13 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 D-1 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 D-1 North 1/4 Corner Section 5, T. 4 N., R. 8 E. Found "T" Iron.

Previously Recorded in L. 13162 P. 799 (4) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

This corner location, although not established by an original government survey, is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 Set Monument and Remonumentation Cap.
- S 75° E 25.19' Set MAG Nail & Remonumentation Disc in North face of Utility Pole.
- S 50° E 4.21' Set MAG Nail & Remonumentation Disc in North face of Fence Post.
- S 25° E 40.94' Set MAG Nail & Remonumentation Disc in West face of 12" Apple.
- S 05° E 12.68' Set MAG Nail & Remonumentation Disc in East face of Fence Post.
- East 47.03' Found Iron Rod & Obliterated Cap South 1/4 Corner Section 32, T. 5 N., R. 8 E., Groveland Twp.
- S 50° E 4.66' Found 1/2" Iron Rod.



Signed by _____
 Surveyor's Michigan License No. 22445

Date March 16, 1998

G.W. FILE
 200