

MAY 24 2000

DE -4 98 34 76 51

SECTION

LIBER 19238PG007

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland

(County)

Located in:

Corner Code #

1. Public Land Survey

T 4N R 8E

G-1

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

\$ 9.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

4 DEC 98 8:35 A.M. RECEIPT# 48

PAID RECORDED - OAKLAND COUNTY

G. WILLIAM CADELL

CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 4-08-98 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Grant J. Ward, R.L.S., in a field survey on October 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Northeast Corner of Section 4, T. 4 N., R. 8 E. Found 1-1/4" Iron Pipe with 5/8" Rod Inside 2' +/- South of Utility Pole.

Previously Recorded in L. 7455 P. 858 (2) of Oakland County Records.

This corner location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 Set Monument and Remonumentation Cap.
- N 30° E 32.59' Set MAG Nail & Remonumentation Disc in South Edge of Concrete Walk.
- S 15° E 81.62' Set MAG Nail & Remonumentation Disc in Southwest face of Utility Pole.
- S 85° W 71.87' Set MAG Nail & Remonumentation Disc in South face of 12" Clump Boxelder.
- N 45° W 2.12' Set MAG Nail & Remonumentation Disc in Northeast face of Utility Pole.
- N 85° W 83.94' Found Frost Pin Southwest Corner of Section 34, T. 5 N., R. 8 E., Groveland Township.



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 22445

Date February 17, 1998

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

900 FILE  
200