

LIBER **19012** PC **358**
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland Located In: Corner Code #
 (county)

1. Public Land Survey T 4N R 8E I-13
 T R
 T R
 T R SURVEY &
 2. Property Controlling S T R REMONUMENTATION
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R MAR 21 2000

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 2 OCT 98 8:45 A.M. RECEIPT# BA
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 11-8-97 JS
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James E. Kovas, in a field survey on September 23, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-13
- 1823- Government Land Office (G.L.O) Wampler, D.S, set standard corner post on township line
- 1874- Walter Neumann #9435 (Survey Liber 6395 Page 847), found 1" iron pipe

Distances: I-13 to H-13 2661.08' (Wade-Trim - 1997)
 I-13 to J-13 2640.23' (Neumann - 1974)(I-13 on the Neumann survey is actually I-1)
 I-13 to J-13 2652.84' (Wade-Trim - 1997)
 I-13 to I-1 (White Lake) 17.82' east (27 links GLO)
 I-13 to I-1 (White Lake) 17.82' east (Wade-Trim - 1997)
 (reset I-13 at the GLO distance I-1)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-13 Set iron

WITNESSES FOUND: This corner was reset at the GLO distance of 17.82' west of I-1 on line between I-1 and H-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Set 5/8" iron rod with Remon Cap #33138

- WIT: S 75 E 61.47' Set 40d nail/Remon Tag #33138 N face 18" Red Oak
- N 15 E 16.15' Set 40d nail/Remon Tag #33138 W face 6" Elm
- S 60 W 40.01' Set 40d nail/Remon Tag #33138 N face 32" Red Oak
- East 17.82' I-1 T3N, R8E 5/8" iron rod with Remon Cap #33138
- S 10 W 80.32' Set 40d nail/Remon Tag #33138 E face utility pole



Signed by James E. Kovas Date 9/16/98

Surveyor's Michigan License No. 33138

LIBER 19012 PC 358