

Part Springfield

LIBER 21143 073
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

58665

For Corners in

Oakland
 (County)

Located in:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|----|------|
| 1. Public Land Survey | T | 4N | R | 8E | J-11 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

LIBER 21143 PAGE 73
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 02/28/2000 01:52:10 P.M. RECEIPT# 162
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF

Approved by
 ACT 363, P.A. 1999

APPROVED ON: 2-24-99
 OAKLAND COUNTY REMONUMENTATION
 FIELD CHECK COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Grant J. Ward, R.L.S., in a field survey on March 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-11 Post, per G.L.O. Notes.

SURVEY &
 REMONUMENTATION

MAY 24 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 North 1/4 Corner of Section 35, T. 4 N., R. 8 E.

Previously unrecorded.

This corner location is a careful & faithful reestablishment of the position of the original corner by single proportion measurement by the contractor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-11 Set Monument and Remonumentation Cap.
 N 05° E 37.00' Set MAG Nail & Remonumentation Disc in Southwest face of 26" Oak.
 S 25° E 23.21' Set MAG Nail & Remonumentation Disc in Southwest face of 26" Oak.
 West 90.78' Set MAG Nail & Remonumentation Disc in Southeast face of 26" Willow.
 N 20° W 104.43' Set MAG Nail & Remonumentation Disc in Southeast face of 26" Oak.
 N 65° W 63.72' Found P.K. Nail in Centerline of Andersonville Road.



Signed by _____
 Surveyor's Michigan License No. 22445

Date February 25, 2000