

MAY 24 2000  
Part of Field SECTION

LIBER 21143 075

58666

LAND CORNER RECORDATION CERTIFICATE LIBER 21143 PAGE 75  
Filing Requirement of Act 74, Mich. P.A. 1970

\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
02/28/2000 01:52:10 P.M. RECEIPT# 16297  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland (County)	Located in:	Corner Code #
1. Public Land Survey	T 4N R 8E	K-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with ACT 345, P.A. 1999  
APPROVED ON: 2-24-99 JS  
OAKLAND COUNTY REMONUMENTATION PERFORMING COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Grant J. Ward, R.L.S., in a field survey on February 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-11 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 Northwest Corner of Section 36, T. 4 N., R. 8 E. Found 5/8" Iron Rod.

Previously Recorded in L. 6596 P. 837 (3) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

This corner location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-11 Set Monument and Remonumentation Cap.
- North 44.95' Set MAG Nail & Remonumentation Disc in East face of 8" oak.
- East 0.57' Set P.K. Nail & Remonumentation Disc in North face of Fence Post.
- N 40° W 48.06' Set MAG Nail & Remonumentation Disc in South face of 14" Cherry.
- N .05° W 11.22' Set MAG Nail & Remonumentation Disc in East face of 28" Oak.
- North 32.96' Found 1/2" Iron Rod.



Signed by \_\_\_\_\_

Date February 25, 2000

Surveyor's Michigan License No. \_\_\_\_\_

22445