

1 FEB 23 98 05 48 8 U

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Oakland (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 4N R 8E M-2  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SECTION**

\$ 7.00 MISCELLANEDUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 23 FEB 98 11:12 A.M. RECEIPT# 1564  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK REGISTER OF DEEDS  
 ACT 345, P.A. 1990

APPROVED ON: 1-14-98 DS  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    |    |    |    |    |    |    |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |

I, James J. Scharl, in a field survey on 11-17, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

|   |   |
|---|---|
| Post set in 1815 G.L.O. survey; 24" W. oak S 22°W 28 lks, LCRC, L 7300, P 646 | 12" W. oak S 79°W 9 lks. LCRC, L 12207, P 881 |
| Stonerock, 1978, 1/2" rerod   | Ward, 1980, iron rod                          |
| *N 80°W 55.66' Nail 18" Locust  | N 40°E 26.82' Spk 14" Oak                     |
| N 20°E 25.79' PK 15" Oak  | *S 25°E 40.83' Spk 10" Oak                    |
| *S 20°E 40.64' PK in 10" Oak  | S 75°W 72.70' Spk Triple 10" Locust           |
|   | *N 70°W 55.50' Spk Twin 10" Locust            |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Recovered 1/2" rerod at the centerline intersection of Knox and Ellis Roads. Distance south to the SE corner of Section 1 (M-3) checks; 2664.05' mea.; 2664.09' survey by Ward, L.7391, P 118, O.C.R.; 2664.09' record.

700 FILE  
200 ✓

**Witnesses Found**

N 34°E 26.48' PK tag 17623 20" Oak  
 N 89°E 23.97' PK tag 17623 50" Locust  
 \*S 26°E 40.77' Nail SW face 16" Oak  
 S 60°W 49.41' PK tag 17623 12" Locust  
 \*N 75°W 55.76' PK tag 17623 18" Locust



\*Confirms LCRC

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

Set 5/8" rerod with O.C. remonumentation cap, replacing 1/2" rerod

|   |                                |
|---|--------------------------------|
| N 60°W 55.33' PK/remon tag S face Twin 12" Locust   | <u>State Plane Coordinates</u> |
| N 34°E 26.75' PK/remon tag W face 16" Oak           | N 468559.3195                  |
| S 25°E 40.82' PK/remon tag SW face 14" Oak          | E 13369598.5505                |
| S 70°W 72.31' PK/remon tag N face Triple 14" Locust |                                |

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group, as established under Act 345 of P.A. 1990.

Signed by James J. Scharl Date December 15, 1997  
 Surveyor's Michigan License No. 19843