

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970; 7.00 MISCELLANEOUS RECORDING

For corners in
Oakland
(County)

Located In:

Corner Code #

\$ 2.00 REMONUMENTATION
23 FEB 98 11:13 A.M. RECEIPT# 156A.
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS.

1. Public Land Survey	T	<u>4N</u>	R	<u>8E</u>	<u>M-9</u>
	T		R		<u>SURVEY &</u>
	T		R		<u>REMONUMENTATION</u>
	T		R		
2. Property Controlling in Section	S		T		<u>MAR 21 2000</u>
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		<u>SECTION</u>

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-14-98 53
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, James J. Scharl, in a field survey on 11-17, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1815 G.L.O. survey; 12" W. oak S 12"W 66 lks; 12" W. oak N 40°E 71 lks.
LCRC, L 7484, P 680
Petrie, 1979, 5/8" rerod
S 85°E 32.94' 7" Oak
*S 20°W 33.60' 50" Oak
*S 70°W 11.70' 13" Oak
*N 25°W 20.70' 16" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered concrete monument as referenced in "Lake Maria Woods", recorded in L 172, P 20-22, O.C.R.

Witnesses Recovered

N 55°W 22.25' PK N 14" Oak
*N 25°W 20.68' PK S 20" Oak
S 85°E 55.35; PK S 44" Oak
*S 20°W 33.60' PK E 58" Oak
*S 70°W 11.68' PK N 18" Oak
!North 304.79' Conc. monument

*Confirms LCRC !Confirms "Lake Maria Woods"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set O.C. remonumentation cap on existing concrete monument
55°W 22.25' PK/remon tag S face 14" Oak State Plane Coordinates
N 25°W 20.12' PK/remon tag NE face 20" Oak N 449959.7582
S 85°E 55.35' PK/remon S face 40" Oak E 13370370.9537
S 20°W 33.60' PK/remon tag E face 58" Oak
S 70°W 11.68' PK/remon tag N face 18" Oak

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl
Surveyor's Michigan License No. 19843

Date DECEMBER 15, 1997



700 FILE