

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland
(County)

Located In:

Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

23 FEB 98 11:14 A.M. RECEIPT# 156A

PAID RECORDED - OAKLAND COUNTY

LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- | | | | | | |
|--------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>8E</u> | <u>M-10</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Compliance with ACT 345, P.A. 1990

APPROVED ON: 1-14-98 SS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	0	1	2	3	4	5	6	7	8	9	10
3	11	12	13	14	15	16	17	18	19	20	21
4	22	23	24	25	26	27	28	29	30	31	32
5	33	34	35	36	37	38	39	40	41	42	43
6	44	45	46	47	48	49	50	51	52	53	54
7	55	56	57	58	59	60	61	62	63	64	65
8	66	67	68	69	70	71	72	73	74	75	76
9	77	78	79	80	81	82	83	84	85	86	87
10	88	89	90	91	92	93	94	95	96	97	98
11	99	100	101	102	103	104	105	106	107	108	109
12	110	111	112	113	114	115	116	117	118	119	120
13	121	122	123	124	125	126	127	128	129	130	131

I, James J. Scharl, in a field survey on 11-18, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|--------------------------------|
| Post set in 1815 G.L.O. survey; 14" W. oak N 69°W 71 lks; | 14" W. Oak S 79°W 66 lks. |
| LCRC, L 6868, P 370 | LCRC, L 7466, P 148 |
| Heil, 1977, 1/2" iron rod | Williams, 1979, 3/8" rerod |
| NW 1" pipe 39.48' | West 15.03' nail N 6" Cherry |
| East Pipeline sign 29.20' | N 85°E 61.72' nail N 30" Oak |
| South 1/2" iron rod 33.02' | *N 20°W 29.70' nail NE 36" Oak |
| West Nail 8" stump 15.00' | *N 10°W 29.31' N/disc 28" Oak |

All disc #22645

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" rerod, reset in February of 1997, approximately 5 ft south of the south edge of Foster Road. Corner falls on the extension of a north-south tree row. Corner was reestablished from local surveys

Witnesses Found

- | | |
|--------------------------------------|-----------------------------------|
| *N 05°E 64.84' PK/disc E 12" Hickory | *N 10°W 29.16' PK SE face 36" Oak |
| *S 45°W 21.90' PK/disc N 10" Maple | S 10°W 9.75' PK E face 4" Maple |
| *N 10°W 29.31' PK/disc SE 36" Oak | S 60°W 21.90' PK N face 10" Maple |
| | N 70°W 74.40' PK S face 36" Maple |

*Verifys LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set concrete monument w/O.C. remonumentation cap, replacing 5/8" rerod.

- | | |
|---|-------------------------|
| N 70°W 74.40' PK/remon tag S face 36" Maple | State Plane Coordinates |
| N 10°W 29.31' PK/remon tag E face 36" Oak | N 447311.5644 |
| N 05°E 64.84' PK/remon tag W face 12" Hickory | E 13370474.0451 |
| East 65.92' PK/remon tag S face 18" Oak | |
| S 10°W 9.75' PK/remon tag E face 4" Maple | |
| S 45°W 21.93' PK/remon tag N face 10" Maple | |

The selected location is a careful and faithful reestablishment of the position of the original corner. This corner was also accepted by the Oakland County Peer Group, as established under Act 345 of P.A. 1990.

Signed by James J. Scharl
Surveyor's Michigan License No. 19843

Date DECEMBER 15, 1997



700 FILE
200