

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Oakland), Located In, Corner Code (#), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous Property, Lot No., and Private Claims.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 9-27-95 JMS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. A black dot is located at the intersection of column G and row 3.

I, James J. Scharl, in a field survey on 8-9, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817 G.L.O. survey; 8" Hickory S 44°E 17 lks, 8" Hickory N 32°W 3 lks

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 SEP 95 7:29 A.M. RECEIPT# 5B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" rerod 6" below the centerline of the grass covered road surface of abandoned Perry Lake Road within Independence Oaks Park. A rock/tree row runs west from the corner.

Rerod was recovered from measurements shown on 1958 McAlpine Engineering survey of Independence Oaks Park.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with O.C. remonumentation brass cap, replacing the 1/2" rerod.

- N 45°W 22.05' PK/remon tag 24" ash
N 35°E 74.23' PK/remon tag 8" elm
S 45°E 75.47' PK/remon tag 12" ash
S 40°W 25.60' PK/remon tag 28" oak

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corne was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990

Signed by [Signature] Date August 23, 1995
Surveyor's Michigan License No. 19843