

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County) Located In: Corner Code #
1. Public Land Survey T 4N R 9E H-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 9-27-95 JMS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column H and row 13.

I, James J. Scharl, in a field survey on 8-24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817 G.L.O. survey.

N 25°E 2 lks 8" W Oak
S 27°E 40 lks 18" B Oak

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 SEP 95 7:29 A.M. RECEIPT# 58
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner at this location was obliterated. Relocated corner from measurements shown on the "Oakland Ridge Subdivision", L 18, P 34, O.C. Records, and the "Woodhull Lake Subdivision", L 38, P 27, O.C. Records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with O.C. remonumentation brass cap.

N 10°W 39.10' SE corner House #4539
N 05°E 10.97' NW corner House #4533
West 3.78' PK/remon tag S face 28" Oak
S 50°W 25.12' PK/remon tag S face twin 16" Oak

7.00
2.00
RM

The selected location is a careful and faithful reestablishment of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl Date Sept. 26, 1995
Surveyor's Michigan License No. 19843