

**SURVEY &
REMONUMENTATION**

FEB 2956ZU305

LIBER 152357089

MAY - 1 1995 LAND CORNER RECORDATION CERTIFICATE

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 FEB 95 9:43 A.M. RECEIPT# 50B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

Oakland Located In: Corner Code #
(County)

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>4N</u> R <u>9E</u> | <u>I-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

OK - T. SMITH

Compliance with ACT 345, P.A. 1990

APPROVED ON: 1-25-95
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James J. Scharl, in a field survey on December 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817 G.L.O. survey	LCRC, L7177, P609
N 74°W 89 lks, 18" W Oak	Jones, 1978
S 37°E 79 lks, 28" B Oak	Found 3/8" iron pipe
	*N 40°W 39.14' nail NE side Cherry
	West 26.85' nail N side corner post
	S 50°W 32.61' nail N side 4" Hickory

*100
200
76*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 3/4" iron pipe below the gravel surface on the centerline of Pine Knob Road. A fence/tree row runs west from the corner.

Witnesses Found

- *N 40°W 39.23', nail NE face 14" Cherry
- West 37.81', nail S face 10" Cherry
- S 30°W 33.62', nail W face 10" Hickory
- S 20°W 59.84', nail E face 10" Hickory



*Confirms LCRC witness

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with Oakland County remonumentation brass cap, replacing the 3/4" iron pipe.

- N 40°W 39.17' PK/remon tag E face 14" Cherry
- S 30°W 33.50' PK/remon tag NW face 10" Hickory
- West 37.82' PK/remon tag S face 10" Cherry
- S 45°E 109.85' NW cor house #8550

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl Date Dec. 28, 1994
Surveyor's Michigan License No. 19843