

**SURVEY & REMONUMENTATION**

LIBER **15235** PG **093**

FEB 295020309

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
2 FEB 95 9:43 A.M. RECEIPT# 50B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in **COMMISSION**  
Oakland  
(County)

Located In: Corner Code ##

1. Public Land Survey	T	<u>4N</u>	R	<u>9E</u>	<u>I-10</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

**OK - T. SMITH**

Compliance with ACT 345, P.A. 1990

APPROVED ON: 1-25-95  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James J. Scharl, in a field survey on December 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817  
G.L.O. Survey  
N 12°E 6 lks, 16" W Oak  
S 46°E 29 lks, 13" W Oak

O.C.R.C. from M.S.H.D., 1958  
1" rod, 2" below surface  
\*East 2.12' P. pole  
S 60°E 50.53' SW cor gar  
S 35°E 90.83' clothes post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered concrete monument at corner of chain link fence, running south and east.

Witnesses Found

\*S 88°E 2.11' N/tag S face DE pole  
N 50°E 96.85' SW house corner #5995 Dvorak  
S 70°E 59.58' SW garage cor

\*Confirms O.C.R.C. witness

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County remonumentation brass cap on existing concrete monument.

East 2.15' PK/remon tag N face DE pole  
South 116.45' PK/remon tag W face DE pole  
N 05°W 150.03' PK/remon tag W face 10" Cherry  
N 50°E 96.67' SW corner house #5995

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl Date Dec. 28, 1994

Surveyor's Michigan License No. 19843

