

SEP 29 1995 188809

LIBER 15709 PG 018

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Oakland (County), Located In:, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 9-27-95 Tom S
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, James J. Scharl, in a field survey on 8-9, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column H and row 11.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817 G.L.O. survey
4" Black oak N 78°W 27 lks
4" Black oak S 35°E 51 lks



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" rerod in monument box on centerline of Maybee Road. Fence lines run north and south. Corner is the SW corner of "Wilshire Sub", recorded in L 79, P 40, O.C. Records, and the NE corner of "Lake Oakland Woods No. 1", recorded in L 151, P 31, O.C. Records. Concrete monuments found North 60.00 ft and South 102.00 ft confirming the corner.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 SEP 95 7:30 A.M. RECEIPT# 5B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" rerod with O.C. remonumentation brass cap set in monument box.
North 58.60' PK/remon tag E face u. pole
N 60°W 96.35' PK/remon tag NE face u. pole
S 40°W 79.70' PK/remon tag N face 10" elm
S 45°E 48.50' PK/remon tag NW face 20" maple
North 60.00' concrete monument

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by [Signature] Date August 21, 1995
Surveyor's Michigan License No. 19843