

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County) Located in: Corner Code #
1. Public Land Survey T 4N R 9E I-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 9-27-95 JMS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, James J. Scharl, in a field survey on 8-9, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column 34 and row 12.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817 G.L.L. survey
10" W. oak S 28°E 30 lks
12" W. oak N 31.5°E 67 lks

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 SEP 95 7:30 A.M. RECEIPT# 58
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" rerod NW'ly 14.3 ft from the edge of the asphalt cul-de-sac of Timber Ridge Circle in the "Timbers of Lake Oakland" condominium subdivision recorded in L 12679, P 712-716. This corner is also the SE corner of "Lake Oakland Woods No. 4", recorded in L 165, P 40-41, O.C. records. Distances measured to north confirm the location.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with O.C. remonumentation brass cap, replacing 1/2" rerod.
N 10°E 2.52' PK/remon tag SE face 14" cherry
S 60°W 31.00' PK/remon tag E face 18" oak
N 50°W 29.92' PK/remon tag N face 14" cherry
East 88.23' PK/remon tag S face 10" elm

Handwritten note: 7.00, 2.00, Rmt

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl Date August 28, 1995
Surveyor's Michigan License No. 19843