

**SURVEY & REMONUMENTATION**

MAY - 1 1995

LIBER 15235-095

25020317

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISCELLANEOUS RECORDING  
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in **COMMISSION**

2 FEB 95 9:44 A.M. RECEIPT# 50B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

**OK - T. SMITH**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-25-95  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

Oakland (County)	Located In:	Corner Code #
1. Public Land Survey	T 4N R 9E	J-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James J. Scharl, in a field survey on December 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1817	LCRC, L12067, P015
G.L.O. survey	Scharl, 1991
S 68°W 30 lks 6" B Oak	Found 1/2" pipe
N 79°E 74 lks 6" B Oak	N 10°E 15.18' nail SE side 24" Oak
	*East 19.42' nail S side 30" Oak
	S 20°E 20.60' nail SW side 36" Oak
	*West 19.36' nail N side 6" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" pipe at the intersection of a north-south and east-west fence/tree line. A rock row runs west from corner.

Witnesses Found

N 10°E 14.89' PK E face 14" Sassafras  
\*N 85°E 19.45' PK S face 18" Oak  
S 15°E 20.16' PK W face 26" Oak  
\*S 80°W 19.37' nail N face 7" Ironwood

\*Confirms LCRC witness

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County remonumentation brass cap, replacing 1/2" pipe.

N 10°E 15.00' PK/remon tag E face 14" Sassafras  
N 85°E 19.47' PK/remon tag S face 18" Oak  
S 15°E 20.08' PK/remon W face 26" Oak  
S 80°W 19.30' PK/remon tag N face 7" Ironwood

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl Date Dec. 28, 1994  
Surveyor's Michigan License No. 19843

