

**SURVEY & REMONUMENTATION**

LIBER 15235 PG 100

25020316

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE** \$ 7.00 MISCELLANEOUS RECORDING  
 Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in **COMMISSION**

2 FEB 95 9:44 A.H. RECEIPT# 50B  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Oakland (County)	Located In:	Corner Code ##
1. Public Land Survey	T 4N R 9E	K-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**OK - T. SMITH**

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 1-25-95  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, James J. Scharl, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Post set in 1817 LCRC, L7177, P610, Jones, 1978  
 G.L.O. survey 10" long mon. in centerline road  
 S 72°W 54 lks 20" Elm \*S 45°W 24.02' 8" Ash  
 N 83°E 19 lks 30" W Oak \*S 60°E 17.93' 12" Ash  
 N 45°E 75.72' iron

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Recovered concrete monument referenced in "Round Lake Woods", L47, P33, O.C. Records. The monument is located 4 ft south of the centerline of Whipple Lake Road and 9 ft east of the centerline of Dartmouth Road.

**Witnesses Found**

N 35°E 61.69' PK E face 10" Ash  
 \*S 60°E 17.95' PK N face 14" Ash  
 \*S 60°W 24.04' PK SE face 18" Ash  
 N 55°W 66.78' PK NE face 20" Ash

\*Confirms LCRC witness



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Oakland County remonumentation brass cap on top of existing concrete monument.

N 35°E 61.53' PK/remon tag E face 10" Ash  
 S 60°E 17.90' PK/remon tag N face 14" Ash  
 S 60°W 24.03' PK/remon tag SE face 18" Ash  
 N 55°W 66.61' PK/remon tag E face 20" Ash

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by James J. Scharl  
 Surveyor's Michigan License No. 19843

Date Dec. 28, 1994