

COPY

MAY 16 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

COMMISSION

For corners in

Form with fields for County (Oakland), Located In, Corner Code (M-2), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

\$ 2.00 REMONUMENTATION
23 MAR 95 9:51 A.M. RECEIPT# 148
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 2-15-95
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numerical values from 1 to 36.

I, James J. Scharl, in a field survey on December 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of survey details including post set in 1817 G.L.O. survey, Baldwin Iron pipe, NE 39.15' 6" Oak, NE 41.55' 14" Twin Oak, \*SW 40.2' Gate post, SE 58.3' Gate post, \*SW 40.45' Stone gate post, and descriptions of corner evidence found.

Witnesses Found

- List of witnesses found with bearings and distances: \*N 65°W 51.31' PK/tag S face 20" Oak, N 45°W 59.51' PK/tag S face DE pole, \*N 85°E 83.97' PK/tag S face light pole, \*S 15°E 97.48' PK/tag E face Maple cluster, \*S 40°W 39.50' PK/tag S face DE pole, \*S 45°W 40.44' NW corner, stone gate post

\*Confirms LCRC witness

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" rerod with O.C. remonumentation brass cap in monument box, replacing 1/2" rerod. N 45°W 59.53' PK/remon tag S face DE pole, N 65°W 51.30' PK/remon tag S face 20" Oak, S 40°W 39.30' PK/remon tag S face DE pole, N 85°E 84.12' PK/remon tag S face light pole, S 45°W 40.44' NW corner stone gate post

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by [Signature] Date February 10, 1995
Surveyor's Michigan License No. 19843

