

**SURVEY &
REMONUMENTATION**

LIBER **14960** pg. **104**

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH
94 242134

For corners in **COMMISSION**

Oakland
(County)

Located In: Orion Township Corner Code # A-3

1. Public Land Survey	T	<u>4</u>	N	R	<u>10</u>	E	<u>A-3</u>
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:18 P.M. RECEIPT# 134B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990

APPROVED ON: LS-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy in a field survey on November 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 14" White Oak N46°E 28 Lnks; 18" Black Oak S88°E 19 Lnks
1979-Jones, P.S. #16045; LCRC L.7466, Pg.145 - Fnd 1/2" Iron Rod

[Handwritten signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a 1/2" Iron Rod in a fence line extending North and South.

Two witness points from the 1979 LCRC were found and they were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" iron rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 I replaced the found 1/2" iron rod with a 4" diameter concrete monument 36" long with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

- N58°W-85.31 ft-NE corner of house #9628
- S75°W-89.00 ft-SE corner of house #9628
- N27°W-98.19 ft-South edge of the top of a retaining wall
- S03°W-26.31 ft-Set PK & Remon. Washer in East face 6" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date June 22, 1994

