

COPY

Dec 19 96 306273

LIBER 16850 PG 368

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland

(County)

Located in: Orion Twp Corner Code #

- 1. Public Land Survey T 4N R 10E B-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

MISCELLANEOUS RECORDING REMONUMENTATION 19 DEC 96 10:52 A.M. RECEIPT# 16B PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-26-96 TS OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on 8/20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set Post 8" Cedar N12 E 15 Links; 12" Cedar S05 W 12 Links
1.) 1995-Scharl, PS #19843; LCRC L.15245, Pg.581 - Fnd Concrete Monument
2.) 1995-Kohn, PS #26459; LCRC L.15388, Pg.573 - Fnd Concrete Monument

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd Concrete Monument with 1/2" Iron Pipe in a swamp. This corner is the Northwest corner of "LOST LAKE SUBDIVISION" a plat recorded in Liber 51 of Plats, on page 59 of Oakland County Records. The Northwest corner of Lot 12 is 237.70 feet (R & M) to the South.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found Concrete Monument with 1/2" Iron Pipe.

I accepted the found Concrete Monument with 1/2" Iron Pipe as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

B-7 to C-7 GLO = 40 chains or 2640.00 Ft., 2599.81 Ft. (MEA 1996)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: B-7 I placed a 2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the existing Concrete Monument
N22 E 12.92' Set PK & Remon Washer West face 12" Ash
S68 E 18.56' Set PK & Remon Washer North face 12" Poplar
S15 W 18.44' Set PK & Remon Washer East face 8" Ash
Due West 18.12' Set PK & Remon Washer South face 14" Poplar

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 11-27-96

