

**SURVEY &  
REMONUMENTATION**

LIBER **14960** PG. **102**

**94 242132**

**MAY - 1 1995**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

**OK - T. SMITH**

For corners in **COMMISSION**

<u>Oakland</u> <small>(County)</small>	Located In: <u>Orion</u> Township	Corner Code # <u>C-2</u>
1. Public Land Survey	T <u>4</u> N R <u>10</u> E	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**\$ 7.00 MISCELLANEOUS RECORDING**  
**\$ 2.00 REMONUMENTATION**  
**8 SEP 94 3:17 P.M. RECEIPT# 134B**  
**PAID RECORDED - OAKLAND COUNTY**  
**LYNN D. ALLEN, CLERK/REGISTER OF DEEDS**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-5-94  
**OAKLAND COUNTY REMONUMENTATION**  
**Register of Deeds Stamp & File Number**  
**PEER GROUP COMMITTEE**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on November 9, 19 93  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	•	5	4	3	2	1					
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1817-GLO Wampler, D.S.; Set Post; 6" Aspen N59°E 0.87 Lnks
- 1981-Murphy, P.S. #9657; LCRC L.8112, Pg.582 - Set 2" diameter Iron Pipe in center of Paint Creek Road
- 1981-Murphy, P.S. #9657; Survey L.8112, Pg.585-587 - Same wits as 1981 LCRC
- 1983-Kennedy, P.S. #17623; LCRC L.8535, Pg.725 - Fnd 1/2" Iron Pipe

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 2" Iron Pipe in the center of Paint Creek.

The witness tress still existing, but the witness points were grown over. They were used to recover and verify the found 2" diameter Iron Pipe.

I accepted the found 2" Iron Pipe as the best evidence of the original corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-2 I placed a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623 in a 2" Iron Pipe in Paint Creek.

- S05°E-7.78 ft-Set PK & Remon. Washer West face 8" Elm
- S50°W-11.34 ft-Set PK & Remon. Washer 18" Ash
- N15°E-10.48 ft-Set PK & Remon. Washer SE face 10" Ash
- Due East-24.44 ft-Set PK & Remon. Washer North face 26" Willow

The selected location is accepted by me and is generally accepted by Professional Surveyor HUSTON KENNEDY as the best available evidence of the position of the original position of the corner.

Signed by Huston Kennedy  
 Surveyor's Michigan License No. 17623

Date August 11, 1994

