

SURVEY & REMONUMENTATION

LIBER. **14960** PG. **107**

94 242437

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Oakland
(County)

COMMISSION

Located In: Orion
Township

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>4</u> N | R | <u>10</u> E | <u>C-3</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on November 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3		●									
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 36" White Oak N48°E 18 Lnks; 10" Black Oak S20°W 46 Lnks
1978-Kobs, P.S. #14097; LCRC L.7156, Pg.560 - Fnd 1 1/2" Pipe
1981-Murphy, P.S. #9657; LCRC L.8112, Pg.582 - Fnd 1 1/2" Iron Pipe
1981-Kobs, P.S. #14097; Survey L.7156, Pg.558 - Same wits as 1978 LCRC

[Handwritten signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


1993 - Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd that the 1 1/2" iron pipe had been removed due to excavation to create a pond. Based upon an unrecorded Certificate of Survey, I made on January 14, 1981, I set a reference corner on the South line of Section 5 20.00 feet East of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3 I placed a 4" diameter concrete monument 36" long w/2" diameter cap stamp
Remonumentation P.S. #17623.

S10°W-19.22 ft-Set PK & Remon. Washer East face 8" Maple
S05°W-10.13 ft-Set PK & Remon. Washer West face 4" Ash
S50°E-31.96 ft-Set PK & Remon. Washer NE face 9" Elm
S60°E-42.61 ft-Set PK & Remon. Washer NE face 9" Elm

The selected location for this property controlling monument is accepted as a faithful determination of the position as indicated.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date June 27, 1994