

**SURVEY &
REMONUMENTATION**

LIBER 14960 pc 108

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 242438

OK - T. SMITH

For corners in

COMMISSION

Oakland
(County)

Located In: Orion Corner Code #
Township

1. Public Land Survey	T	4	N	R	10	E	D-1
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:18 P.M. RECEIPT# 1348
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990

APPROVED ON: 15-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on November 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		1
5											
6	18		17		16		15		14		1
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 15" Pine N26°E 44 Lnks; 12" Pine S29°W 4 Lnks
1974-Albright, P.S. #10057; LCRC L.6373, Pg.882-883 - Fnd 1" Square Head Bolt
1976-Kennedy, P.S. #17623; Survey L.6775, Pg.192-194 - Found 1" Iron Rod
1976-Kennedy, P.S. #17623; LCRC L.6821, Pg.467 - Same wits as 1976 survey
1976-Kennedy, P.S. #17623; Survey L.6821, Pg.470-472 - Same wits as 1976 survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a 1" Bolt Spike that is 3'± North of the center of Stanton Road, which is gravel surface.

The witness points from the 1976 LCRC are still existing and they were used to recover and verify the found 1" Bolt Spike.

I accepted the found 1" bolt spike as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 I replaced the found 1" bolt spike with a 5/8" x 24" iron rod with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

N54°E-29.46 ft-Set PK & Remon. Washer below existing witness SE face 4" Cherry (in clump of 6)
N55°W-73.84 ft-Set PK & Remon. Washer SW face 8" Cherry
S39°E-50.39 ft-Set PK & Remon. Washer NE face 12" Pine
S68°E-58.82 ft-Set PK & Remon. Washer above existing witness North face 6" Oak

The selected location is accepted by me and is generally accepted by _____ as the best available evidence of the position of the original position.

Signed by

Huston K. Kennedy

Date June 22, 1994

Surveyor's Michigan License No. 17623

