

MAY 9 1997  
COPY  
COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

9.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
3 JAN 97 7:45 A.M. RECEIPT# 7B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland

(County)

Located In Orion Twp Corner Code #

1. Public Land Survey

T	4	N	R	10	E	E-6
T		R				
T		R				
T		R				
S		T		R		
S		T		R		
S		T		R		
S		T		R		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 12-17-96 TS.  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 11/20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	10		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 12" Black Oak S74°W 67 Links; 3" White Oak N77°E 107 Links  
1.) 1979-Giffels-Webster Engineers, Inc. - Object found not stated, no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was recovered by holding the position as shown on the Boundary Survey of "ORION HILLS" is 2 feet ± East of the centerline of a North-South path and 80 feet ± South of the intersection of a North, South, East & West path. There are no lines of occupation.

Boundary Survey for "ORION HILLS" was used to recover and verify the location of the set 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.

I accepted the set 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 as the best evidence of the original corner position.

Field Measurements see back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-6 I set a 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
- S21°E 194.92' Set PK & Remon Washer SW face 10" Elm
- S17°W 229.55' Set PK & Remon Washer SW face 13" Cherry
- S54°W 195.92' Set PK & Remon Washer SE face clump of 10" Cherry
- N76°W 86.10' Set PK & Remon Washer North face 7" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date 12-18-96



**COPY**

LIGER **16874PG108**

**SURVEY &  
REMONUMENTATION**

**MAY 22 1997**

**COMMISSION**

FIELD MEASUREMENTS BETWEEN

E-6 to E-5 GLO = 40 chains or 2640.00 Ft., 2708.93 Ft. (GWE 1979) 2708.93 Ft. (NEA 1996)  
E-6 to E-7 GLO = 40 chains or 2640.00 Ft., 2685.21 Ft. (GWE 1979) 2684.50 Ft. (NEA 1996)