

SURVEY & REMONUMENTATION

LIBER **14960** PG **111**

94 242441

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in **COMMISSION**

<u>Oakland</u> <small>(County)</small>	Located In:	Orion Township	Corner Code # F-1
1. Public Land Survey	T <u>4</u> N R <u>10</u> E		
	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
2. Property Controlling in Section	S ___ T ___ R ___		
	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:19 P.M. RECEIPT# 134B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK, REGISTER OF DEEDS
APPROVED ON: 1-5-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on November 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 12" White Oak S16°W 36 Lnks; 4" Black Oak N52°E 26 Lnks
1990-Patterson, P.S. #17631; LCRC L.11621, Pg.701 - Fnd 1" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a concrete monument.

All witnesses are existing and they were used to recover and verify the found concrete monument that has replaced the 1" iron.

I accepted the found concrete monument as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 I placed a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623 on the found concrete monument.

- N08°W-19.19 ft-Set PK & Remon. Washer in East face Power Pole
- N75°W-28.94 ft-Set PK & Remon. Washer in South face 19" Oak
- S45°W-24.54 ft-Set PK & Remon. Washer in East face 10" Pine
- S33°E-47.28 ft-Set PK & Remon. Washer in NE face 9" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.

Signed by

Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date June 22, 1994



	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Handwritten initials/signature