

COPY

LIBER 16910 PG 381

JAN 15 97 01 1982

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located in: Orion Twp Corner Code # (Ref. corner)

- 1. Public Land Survey T 4N R 10E G-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 JAN 97 8:32 A.M. RECEIPT# 21A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN REGISTER OF DEEDS
ACT 345, P.A. 1990
APPROVED ON: 12-30-96 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on 12/23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; No post set, corner falls in a lake

SURVEY &
REMONUMENTATION

MAY 22 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
See back of LCRC

FIELD MEASUREMENTS BETWEEN

- G-6 to G-5 GLO = 40 chains or 2640.00 Ft., 2785.33 Ft. (Calculated)
G-6 to G-7 GLO = 40 chains or 2640.00 Ft., 2764.82 Ft. (Calculated)
G-7 to reference corner 2564.82 Ft. (GPS-NEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6 I set a 4" diameter Concrete Monument with a 1/2" Iron 36" long w/2" diameter brass cap stamped Oakland County Remonumentation PS #17623 as a reference corner 200.00 feet South of G-6
N52°E 6.36' Set PK & Remon Washer NW face 10" Oak
Due North 10.09' Set PK & Remon Washer East face 10" Oak
N22°E 29.91' Set PK & Remon Washer West face 14" Oak
N39°E 19.28' Set PK & Remon Washer NW face 9" Oak

The selected location for this reference corner is accepted as a careful and faithful determination of the position as indicated

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 31, 1996



GLO FILE
200

**COPY**

LIBER 16910 PG 382

HOW THE CORNER WAS RECOVERED

Researching the Oakland County Records for Land Corner Recordation Certificates (LCRC) and Certificates of Survey shows that nothing has been recorded for this corner. I did not receive any information from other sources regarding this corner. However, I did recover Warranty Deed recorded in Liber 535, on pages 523 & 524 on October of 1926.

I used the above mentioned Warranty Deed to recover this corner, I set a reference corner on the line between Sections 15 & 16, 200 feet South of the corner, which is located 19 feet  $\pm$  South of the water's edge.

SURVEY &  
REMONUMENTATION

MAY 22 1997

COMMISSION