

Hand/Car
**SURVEY &
 REMONUMENTATION**

JAN 20 95 011166

LISER 15212 PC 852

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

Filing Requirement of Act 74, Mich. P.A. 1970 7.00

MISCELLANEOUS RECORDING

For corners in

Oakland
(County)

COMMISSION

Located In: Orion
 Twp.

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>10E</u> | <u>G-8</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

\$ 2.00 REMONUMENTATION
 20 JAN 95 7:26 A.M. RECEIPT# 5B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 9-14-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on August 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; White Oak N79*W 18 Links; 24" White Oak S42*E 8 Links
 1.) 1973-Stonerock, P.S. #13601; LCRC L.6212, Pg.266 - Fnd 1/2" Iron
 2.) 1973-Stonerock, P.S. #13601; Survey L.6212, Pg.252 & 253 - Fnd 1/2" Iron Rod, same wit as 1973 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 1.80' South to the centerline of Greenshield Road a 15' wide gravel road and 24.93' North to a fence corner that extends North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accept the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-8 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P. #17623.
 S40°E 30.60' Set PK & Remon. Washer NE face twin 10" Oak
 S51°W 26.02' Set PK & Remon. Washer SE face 13" Basswood
 N11°E 16.81' Set PK & Remon. Washer SE face twin 21" Basswood
 N27°W 25.59' Set PK & Remon. Washer SW face twin 12" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston K. Kennedy*

Date December 17, 1994

Surveyor's Michigan License No. 17623