

**SURVEY & REMONUMENTATION**

LIBER 15225 PGC 653

JAN 27 95 016439  
OK - T. SMITH

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE** \$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Oakland  
(County)

**COMMISSION**

Located in: Orion Corner Code ##  
Twp.

27 JAN 95 11:01 A.M. RECEIPT# 76B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

1. Public Land Survey	T <u>4N</u> R <u>10E</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-29-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on December 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Notes Wampler, D.S.; Set Post 10" White Oak N70°E 51 Chains; 4" Black Oak S73°W 32 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994-Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod at an old fence corner with fence-tree line extending to the North & West.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

**FIELD MEASUREMENT BETWEEN**

G-9 to H-9 2699.38 Ft. (H. Kennedy 1994)  
GLO = 40.945 Chains (2702.37 Ft.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 I replaced the found 1/2" Iron Rod with 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.  
S87°W 4.14' Set PK & Remon. Washer SE face 29" Oak  
S03°W 51.95' Set PK & Remon. Washer West face 9" Pine  
N48°W 7.65' Set PK & Remon. Washer NE face 18" Oak  
N31°E 11.25' Set PK & Remon. Washer NW face 8" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date January 11, 1995