

SURVEY & REMONUMENTATION

LIBER 15225 PG 654

JAN 27 1995 016440

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
27 JAN 95 11:01 A.M. RECEIPT# 76B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in
Oakland
(County)

COMMISSION

Located In: Orion Corner Code #
Twp. G-11

1. Public Land Survey	T	4N	R	10E	G-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 9-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
OK - T. SMITH
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on December 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 18" Tamarac N35°E 37 Links; 18" Tamarac S09°E 17 Links
 1.) 1980-O'Rourke, P.S. #16937; LCRC L.7771, Pgs.609-610 - Fnd 3/4" Iron Pipe
 2.) 1991-Hoben, P.S. #35994; LCRC L.12236, Pg.224 - Fnd 1" Iron
 3.) 1992-Kennedy, P.S. #17623; LCRC L.12730, Pg.862 - Fnd 1" Iron Pipe w/capped Iron inside
 4.) 1980-O'Rourke, P.S. #16937; Survey L.7766, Pg.179 - Fnd 3/4" Iron Pipe, used same wit as 1980 LCRC
 5.) 1981-Finney, P.S. #15536, Survey L.7975, Pg.253 - Fnd 3/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod.

Witnesses from LCRC #1 & 3 were used to recover and verify the location of the found 5/8" Iron Rod.

I accept the found 5/8" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-11 I replaced the found 5/8" Iron Rod with a 5/8" x 60" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation PS #17623.
 S41°W 47.81' Set PK & Remon. Washer NW face 11" Elm
 S07°E 64.41' Set PK & Remon. Washer East face 12" Elm
 S31°E 87.56' Set PK & Remon. Washer SW face 27" Poplar
 N52°E 68.57' Set PK & Remon. Washer SE face 10" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date January 11, 1995

