

SURVEY & REMONUMENTATION

LIBER 15212 PG 872

JAN 20 95 011186

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1976

For corners in
Oakland

COMMISSION

Located In: Orion Twp.

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>4N</u> R <u>10E</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 7:33 A.M. RECEIPT# 78
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-29-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on September 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 6" White Oak N24°E 14 Links; 14" Black Oak S32°W 20 Links
 1.) 1978-Lippincott, P.S. #25855; LCRC L.7372, Pg.854 - Fnd 5/8" Re-rod in a Monument Box
 2.) 1980-O'Rourke, P.S. #16937; LCRC L.7771, Pg.608 - Fnd 1" Iron Bar in a Monument Box
 3.) 1990-Wozniak, P.S. #15066, P.S. LCRC L.11580, Pg.542 - Set capped Iron Rod (in accordance w/survey recorded in L.7766, Pg.179 Oakland County Records)
 4.) 1980-O'Rourke, P.S. #16937; Survey L.7766, Pg.179 - Fnd 1" Iron Bar in a Monument Box, used same wit as 1980 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod with cap #15068 38 feet North on the centerline of Brown Road
 Witnesses from LCRC #1 & 3 were used to recover and verify the location of the found 1/2" Iron Rod with cap #15068.
 I accepted the found 1/2" Iron Rod with cap #15068 as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 I replaced the found 1/2" Iron Rod with a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
 N51°W 97.69' Set PK & Remon. Washer SW face 9" Ash
 N05°W 37.41' Set PK & Remon. Washer West face Twin 17" Ash
 N38°E 47.84' Set PK & Remon. Washer SE face 14" Pear
 S31°W 24.10' Centerline c/b on North side of Brown Road

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date January 9, 1995

