

**SURVEY &
REMONUMENTATION**

JAN 27 1995 016447

LIBER 15225 PG 655

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

27 JAN 95 11:01 A.M.

RECEIPT# 76B

PAID

RECORDED - OAKLAND COUNTY

LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-29-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

For corners in **COMMISSION**

Oakland (County)	Located In:	Orion Twp.	Corner Code #
1. Public Land Survey	T 4N	R 10E	H-7
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on December 20, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 17" Black Oak S78°E 34 Links; 36" White Oak N51°W 4 Links
- 1.) 1973-Stonerock, P.S. #13601; LCRC L.6083, Pg.36 - Fnd 1" Iron Rod
- 2.) 1976-Kennedy, P.S. #17623; LCRC L.6821, Pg.467 - Fnd 1" Iron Pipe
- 3.) 1973-Stonerock, P.S. #13601; Survey L.6083, Pg.23 - Fnd 1" Iron Rod, used same wit as 1973 LCRC
- 4.) 1976-Kennedy, P.S. #17623; Survey L.6675, Pg.566 - Fnd 1" Iron Rod, used same wit as 1976 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in the centerline of Scripps Road, which has a gravel surface extending to the East & West. I also found a 1/2" Iron Rod w/cap #17623 on the existing 33' right of way for Scripps Road, and another 1/2" Iron Rod was found 933' East in the center of Scripps Road.

The witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod with as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- H-7 to I-7 2705.53 Ft. (H. Kennedy 1975)
- H-7 to I-7 2706.64 Ft. (G. Stonerock 1973)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
- N79°W 74.55' Set PK & Remon. Washer South face 26" Oak
- N71°E 70.72' Set PK & Remon. Washer South face 22" Oak
- S67°W 74.46' Set PK & Remon. Washer South face 12" Oak
- S73°E 66.11' Set PK & Remon. Washer North face 34" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best professional evidence of the position of the original corner.

Signed by H. Kennedy Date January 12, 1995
Surveyor's Michigan License No. 17623

